



**Annex A: Bill of Quantities**

**Name of Project: CONSTRUCTION OF GENERATOR SET HOUSE FOR BUTTON MUSHROOM BUILDING**

ITEM NO.	DESCRIPTION	QTY	UNIT	Unit Price (in Pesos)	Total Cost (in Pesos)
1700(1)	CLEARING, GRUBBING AND LAY OUT	20.00	sq.m		
803(1)a	STRUCTURE EXCAVATION (Common Soil)	7.14	cu. m.		
804(1)a	EMBANKMENT (from structure excavation)	1.14	cu. m.		
900(1)c2	STRUCTURAL CONCRETE	10.00	cu. m.		
903(2)	FORMS & FALSEWORKS	53.00	sq.m		
902(1)a1	REINFORCING STEEL BARS (Grade 40, deformed)	1,397.94	kgs.		
1046(2)	CHB NON-LOAD BEARING (Including RSB)	103.85	sq.m		
1027(1)	CEMENT PLASTER FINSH	137.95	sq.m.		
1016(1)a	WATERPROOFING	24.37	sq.m		
1032(1)a	PAINTING WORKS	138.80	sq.m		
1100.00	CONDUITS, BOXES, & FITTINGS	1.00	L.s		
1101.00	WIRES & WIRING DEVICES	1.00	L.s		
1102.00	POWER LOAD CENTER, SWITCH GEAR AND PANEL BOARD	1.00	L.s		
B.5	PROJECT BILLBOARD/SIGNBOARD	1.00	set		
<b>TOTAL BID AMOUNT (in figures): Php</b>					
<b>TOTAL BID AMOUNT (in words): Pesos</b>					

**Note:** The Bill of Quantities (BOQ) contains the following parts:  
 a. BOQ for each Part of the Contract.  
 b. Summary of Bid Prices for all Parts of the Contract.

Project Duration: **51 calendar days**

Submitted by:

Name and Signature of Bidder's Representative: \_\_\_\_\_

Position: \_\_\_\_\_

Name of Bidder: \_\_\_\_\_

Date: \_\_\_\_\_