



**Annex A: Bill of Quantities**

**Name of Project: CONSTRUCTION OF NURSERY FOR MASSIVE SEEDS AND SEEDLING PRODUCTION**

ITEM NO.	DESCRIPTION	QTY	UNIT	Unit Price (in Pesos)	Total Cost (in Pesos)
B.1	PROVISION FOR SAFETY & HEALTH	1.00	Ls		
800(1)	CLEARING, GRUBBING AND LAY-OUT	1.00	Ls		
803(1)	STRUCTURE EXCAVATION	6.05	cu.m.		
804(1)a	EMBANKMENT FROM STRUCTURE EXCAVATION	1.35	cu.m.		
804(4)	GRAVEL BEDDING	0.31	cu.m.		
900(1)	STRUCTURAL CONCRETE	2.05	cu.m.		
902(1)a1	REINFORCING STEEL BARS, DEFORMED, GRADE 40	252.39	kgs.		
903(2)	FORMS AND FALSEWORKS	43.68	sq.m		
1002(3)a1-a	GALVANIZED IRON PIPE SCHEDULE 40 (20MM DIA)	45.00	pcs		
1002(3)a2	GALVANIZED IRON PIPE SCHEDULE 40 (25MM DIA)	30.00	pcs		
1002(3)a5	GALVANIZED IRON PIPE SCHEDULE 40 (50MM DIA)	55.00	pcs		
1002(3)a7	GALVANIZED IRON PIPE SCHEDULE 40 (75MM DIA)	17.00	pcs		
1046(2)	CHB NON-LOAD BEARING	49.66	sq.m.		
<b>TOTAL BID AMOUNT (in figures): Php</b>					
<b>TOTAL BID AMOUNT (in words): Pesos</b>					

**Note:** The Bill of Quantities (BOQ) contains the following parts:  
 a. BOQ for each Part of the Contract.  
 b. Summary of Bid Prices for all Parts of the Contract.

Project Duration: **27 calendar days**

Submitted by:

Name and Signature of Bidder's Representative: \_\_\_\_\_

Position: \_\_\_\_\_

Name of Bidder: \_\_\_\_\_

Date: \_\_\_\_\_