



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE

National Road, Purok 6, Bulanao, Tabuk City, Kalinga

Website: <http://kasc.edu.ph> Email: kastatecollege@yahoo.com Contact No.: 0917-822-6145

SUPPLEMENTAL / BID BULLETIN (SBB) NO. 01

This SBB No. 01 dated August 5, 2016 for the Project, "Construction of Gymnasium Phase IV (2nd Bidding)" is issued to clarify, modify or amend items in the Bidding Documents. Accordingly, this shall form an integral part of said Documents.

PARTICULARS	CLARIFICATION / AMENDMENT
<p>Section VI. Specifications</p> <p>Terms of Reference</p> <p>X. Terms of Payment</p> <p>10.4 The retention fund shall be released only upon issuance of Certification of Final Acceptance issued by KSU Infrastructure Unit and submission by Contractor of Post-Construction Documentation.</p>	<p>KSU will be strict for this particular provision.</p>
<p>XII. Scope and Coverage of the Project with Specification</p> <p>I. Clearing, Grubbing and Lay out, 361 sq.m., removal of 1 acacia tree @ front</p>	<ul style="list-style-type: none"> ✓ KSU will appraise the acacia tree and secure permit from DENR prior to cutting and clearing the area. ✓ The Contractor is encouraged to perform a ritual to appease the spirit of the tree before cutting it.
<p>IV. Forms and Scaffoldings, 2,945.83 sq.m.</p>	<p>The corrected Scope of Works shall be:</p> <ul style="list-style-type: none"> ✓ it is suggested that the staging and scaffoldings should be lumber, ✓ all forms and scaffoldings (lumber and plywood) should be turned over to KSU, and ✓ If scaffoldings are made of steel and rented, the Contractor will keep as their own.
<p>VIII. Tinsmithing Works</p> <p>A. Roofing Installation, 454.41 sq.m., which covers unfinished items from grid J to L</p>	<p>The corrected specs of pre-painted roof and accessories are as follows:</p> <ul style="list-style-type: none"> ✓ Ribb type # 0.50mm x 1.20m x 13.4m ✓ Ribb type # 0.50mm x 1.20m x 3.0m ✓ Ribb type # 0.50mm x 1.20m x 12.2m ✓ Ribb type # 0.50mm x 1.20m x 8.06m ✓ Ridge Cap #.50mm x 2.4m ✓ Tek screw (steel) 12mm x 45mm ✓ Blind rivets ✓ End Flashing # 0.50mm x 600mm x 2.40m ✓ Touch up paint
<p>IX. Installation of Doors and Windows</p> <p>A. Windows, 266.76 sq.m., which covers items from grid A-L except @ grid C-J under Bleachers</p>	<p>The corrected specs are as follows:</p> <ul style="list-style-type: none"> ✓ Steel Casement Windows w/ Fixed Glasses ✓ All steel casement should be pre-painted ✓ 12mm square bars for window grills
<p>Section IX. Bidding Forms</p> <p>On Other Bidding Forms particularly the following:</p> <ol style="list-style-type: none"> 1. Bid Schedule, and 2. Construction Schedule and S-Curve 	<p>To include Item No. 1027 - CEMENT PLASTER FINISH</p>

For guidance and information of all concerned.


RAYMOND E. BALBIN, Ph.D.
BAC Chairman

Date Issued: August 5, 2016

Copy furnished: Prospective Bidders